	Area of Network Hierarchy	Area to be treated (m2)													Total Area Treated	Assumed Lane Width of Hierarchy	
			Carriageway Treatments Footway Treatments														
	(m2)	T1 T2	T3	T4	T5	T6	T7	T8	T9	T10	T11	T12	T13	T14	(m2)	(m)	(%)
Primary	2,011,940																
CIP																	
5 Years ending on 5th anniversary of the Planned CIP Completion Date																	
5 Years ending on 10th anniversary of the Planned CIP Completion Date																	
5 Years ending on 15th anniversary of the Planned CIP Completion Date																	
15th anniversary of the Planned CIP Completion Date to the Expiry Date																	
Secondary	2,308,465																
CIP																	
5 Years ending on 5th anniversary of the Planned CIP Completion Date																	
5 Years ending on 10th anniversary of the Planned CIP Completion Date																	
5 Years ending on 15th anniversary of the Planned CIP Completion Date																	
15th anniversary of the Planned CIP Completion Date to the Expiry Date																	
Link	1,168,276																
CIP																	
5 Years ending on 5th anniversary of the Planned CIP Completion Date																	
5 Years ending on 10th anniversary of the Planned CIP Completion Date																	
5 Years ending on 15th anniversary of the Planned CIP Completion Date																	
15th anniversary of the Planned CIP Completion Date to the Expiry Date																	
Local	8,182,972																
CIP																	
5 Years ending on 5th anniversary of the Planned CIP Completion Date																	
5 Years ending on 10th anniversary of the Planned CIP Completion Date																	
5 Years ending on 15th anniversary of the Planned CIP Completion Date																	
15th anniversary of the Planned CIP Completion Date to the Expiry Date																	
High Usage	717,755																
CIP																	
5 Years ending on 5th anniversary of the Planned CIP Completion Date																	
5 Years ending on 10th anniversary of the Planned CIP Completion Date																	
5 Years ending on 15th anniversary of the Planned CIP Completion Date																	
15th anniversary of the Planned CIP Completion Date to the Expiry Date																	
, , , , , , , , , , , , , , , , , , , ,																	
Low Usage	5,740,096																
CIP																	
5 Years ending on 5th anniversary of the Planned CIP Completion Date																	
5 Years ending on 10th anniversary of the Planned CIP Completion Date																	
5 Years ending on 15th anniversary of the Planned CIP Completion Date																	
15th anniversary of the Planned CIP Completion Date to the Expiry Date																	
,																	

- Carriageway Treatment Key
  T1 = Structural Treatment Primary Full Reconstruction including sub base replacement
  T2 = Structural Treatment Primary and Secondary surface coarse, binder coarse and base replacement
  T3 = Structural Treatment Secondary surface and binder coarse replacement
- T4 = Structural Treatment Link and Local surface and binder coarse replacement
- T4 = Structural Treatment Link and Local surface and binder coarse replace
  T5 = Resurfacing Primary surface coarse replacement
  T6 = Resurfacing Secondary, Link and Local surface coarse replacement
  T7 = Micro-Surfacing Primary thin surfacing
  T8 = Micro-Surfacing Secondary thin surfacing
  T9 = Surface Dressing (All hierarchies)
  T10 = Total allowance for premature failures of all treatments

- Footway Treatment Key
  T11 = Full reconstruction (Black)
  T12 = Edge planing and 20mm Overlay or 20 mm Inlay (Black)
  T13 = Full Reconstruction (Other surface finishes)
  T14 = Slurry Seal Surface Treatment